

TOWN OF BENSON RUTLAND COUNTY



EPSC WORK NOTES

- 1 INSTALL STABILIZED CONSTRUCTION ENTRANCE. SEE TYPICAL DETAIL ON SHEET TD-7.
- 2 DEMARCATATE LIMIT OF DISTURBANCE AND INSTALL PERIMETER CONTROLS IN ACCORDANCE WITH GENERAL EPSC NOTES AND CONSTRUCTION METHOD TYPICAL DETAILS ON SHEETS G-5 AND CM-1 THRU CM-5.
- 3 WETLAND CROSSING. SEE "TYPICAL WETLAND CONSTRUCTION" ON SHEET TD-7.
- 4 OPEN TRENCH EXCAVATION OR AT-CULVERT STREAM CROSSING TO BE COMPLETED IN ACCORDANCE WITH TYPICAL DETAILS ON SHEETS TD-4 AND TD-5.
- 5 REPLACE STREAM CULVERT IN ACCORDANCE WITH TYPICAL DETAILS ON SHEETS TD-3 AND TD-4.
- 6 DEMARCATATE AND AVOID POTENTIAL ROOSTING TREE.
- 7 DEMARCATATE AND AVOID RTE POPULATION.
- 8 IMPLEMENT RTE PLANT PROTECTION PLAN.
- 9 IMPLEMENT RTE ANIMAL PROTECTION PLAN.

NOTES

1. CONSTRUCTION LAYDOWN AREA 1 IS LOCATED ON THE SOUTH SIDE OF MILL POND ROAD APPROXIMATELY 2,500 FT EAST OF ROUTE 22A.
2. THE AVAILABLE LAND AREA IS APPROXIMATELY 4.94 ACRES. A PORTION OF THIS AREA INCLUDES WETLAND OR LAND OTHERWISE UNAVAILABLE FOR USE.
3. CONSTRUCTION LAYDOWN SHALL BE DEMARCATATE AND EPSC MEASURES INSTALLED IN ACCORDANCE WITH THE ISSUED PERMITS, EPSC PLAN AND THE USE AGREEMENT WITH THE LAND OWNER.
4. THE LAYDOWN AREA SHALL BE RESTORED TO ITS ORIGINAL CONDITION AT THE COMPLETION OF THE WORK, UNLESS OTHERWISE DIRECTED.
5. EPSC MEASURES AND DEMARCATATE MATERIALS SHALL BE MAINTAINED THROUGHOUT THE DURATION OF THE AREA'S USE.

Designed	.
Drawn	.
Checked	.
Approved	.
Scale	AS NOTED

No.	Revision	Date	By	Ck	PE	PE #
A	ISSUED FOR USE	3/27/15	TRC	AMW		



PLAN  
SCALE: 1" = 100'

**TDI New England**  
A TDI Company

**NEW ENGLAND CLEAN POWER LINK**  
TDI New England  
Construction Laydown

CL-1  
Prepared by: **CTRC** 9/19/14